

ATTACHMENT B



City of Phoenix
PLANNING AND DEVELOPMENT DEPARTMENT

***REVISED**
Staff Report: Z-64-21-8
August 3, 2022

[Camelback East Village Planning Committee Meeting Date](#)

June 7, 2022

[Planning Commission Hearing Date](#)

August 4, 2022

Request From:

[A-2](#) (Industrial District) (17.82 acres)

Request To:

[PUD](#) (Planned Unit Development) (17.82 acres)

Proposed Use

Multifamily residential

Location

Southwest corner of 48th Street and Washington Street

Owner

Lincoln National Life Insurance Company

Applicant

Odyssey Group Holdings, LLC

Representative

Nick Wood, Esq., Snell & Wilmer, LLP

Staff Recommendation

Approval, subject to stipulations

General Plan Conformity			
<u>General Plan Land Use Map Designation</u>		Current: Commerce/Business Park and Industrial	
		Proposed (GPA-CE-2-21-8): Mixed Use	
<u>Street Map Classification</u>	48th Street	Collector	33-foot west half street
	Washington Street	Major Arterial with Light Rail	Varies, 50 to 66.5-foot south half street
CONNECT PEOPLE & PLACES CORE VALUE; TRANSIT ORIENTED DEVELOPMENT; LAND USE PRINCIPLE: Encourage high-density housing and high intensity employment uses to locate adjacent or close to transit stations per adopted transit district plans.			
The proposed development will provide multifamily residential uses near an existing light rail station. This will promote alternative transportation for future residents and guests of this development.			

CONNECT PEOPLE AND PLACES CORE VALUE; COMPLETE STREETS; DESIGN PRINCIPLE: Plan and design communities and neighborhoods to be pedestrian friendly and walkable.

The proposed PUD incorporates numerous streetscape and frontage standards from the Walkable Urban (WU) Code, thus promoting a pedestrian friendly environment along adjacent street frontages.

CONNECT PEOPLE AND PLACES CORE VALUE; BICYCLES; DESIGN PRINCIPLE: Development should include convenient bicycle parking.

The subject site fronts a dedicated bicycle lane on Washington Street, and the proposed PUD narrative requires that secured bicycle parking spaces be provided for residents. The project will support tenants, employees and visitors who use all modes of transportation.

BUILD THE SUSTAINABLE DESERT CITY CORE VALUE; TREES AND SHADE; DESIGN PRINCIPLE: Integrate trees and shade into the design of new development and redevelopment projects throughout Phoenix.

The proposed development provides trees and shade on both street frontages which will reduce the urban heat island effect while also improving thermal comfort to site users and the surrounding neighborhood.

Applicable Plan, Overlays, and Initiatives

[44th Street Corridor Specific Plan](#) – See Background Item No. 9.

[Transit Oriented Development Strategic Policy Framework](#) – See Background Item No. 10.

[Housing Phoenix Plan](#) – See Background Item No. 11.

[Tree and Shade Master Plan](#) – See Background Item No. 12.

[Complete Streets Guiding Principles](#) – See Background Item No. 13.

[Comprehensive Bicycle Master Plan](#) – See Background Item No. 14.

[Zero Waste PHX](#) – See Background Item No. 15.

Surrounding Land Uses/Zoning		
	<u>Land Use</u>	<u>Zoning</u>
On Site	Vacant	A-2
North (Across Washington Street)	Office	A-2 (Approved C-2 M-R)
South (across South Pacific Railroad)	Warehousing and distribution	A-2
East (Across 48th Street)	Various commercial uses and warehousing	A-2
West	SR-143 freeway	A-2

Background/Issues/Analysis

SUBJECT SITE

1. This request is to rezone a 17.82-acre site located on the southwest corner of 48th Street and Washington Street from A-2 (Industrial District) to PUD (Planned Unit Development) to allow multifamily residential and other permitted uses as listed in the Walkable Urban Code Transect T5:5. The site is presently vacant and is located within a quarter mile of the 50th Street / Washington Street light rail station. Furthermore, the site is located adjacent to the SR-143 freeway.
2. The General Plan Land Use Map designation for the subject site is Industrial, thus the proposal is not consistent with this General Plan Land Use Map designation. A companion General Plan Amendment request (GPA-CE-2-21-8) proposes a Land Use Map designation of Mixed Use. The Mixed Use designation calls for multifamily residential and commercial land uses. If approved, the proposal would be consistent with the Mixed Use designation.



General Plan Land Use Map
Source: City of Phoenix Planning and Development Department

The General Plan Land Use Map designation to the north and northwest, across Washington Street, is Mixed Use. South and east of the site, across the Union Pacific Railroad tracks and across 48th Street, is designated as Industrial. The designation along the SR-143 freeway is Transportation.

3. The site is zoned A-2 (Industrial District) and is currently vacant. Properties to the north and northwest of the site, across Washington Street, are zoned A-2 and PUD (Planned Unit Development). Office and multifamily uses are located on those parcels. Properties to the south, east and west of the site are zoned A-2. Land uses include office, restaurants, warehousing and the SR-143 freeway.

C-2 M-R*
HGTWVR
DWSMVC
2:115-07
2:6-07
Target
Citywide District
supplement (2024)

A-2*
Z:13-20

C-2 M-R*
Z:115-07

A-2
HP-L
Z:110-03

A-2
HP-L
Z:110-03

A-2 HP

A-2
HP-L
Z:110-03

PUD
Z:13-54
Z:20-08
Z:20-17
Z:20-56
Z:20-115

WASHINGTON ST

MADISON ST

40TH ST

A-2 HP

A-2 HP
Z:23-14

A-2
HP
Z:103-03

A-1
HP-L
Z:110-04

A-1
HP-L
Z:110-04

Municipal County Assessor's Office

**Zoning Map, Source: City of Phoenix
Planning and Development Department**

4. The proposal was developed utilizing the PUD zoning district. The Planned Unit Development (PUD) is intended to create a built environment that is superior to that produced by conventional zoning districts and design guidelines. Using a collaborative and comprehensive approach, an applicant authors and proposes standards and guidelines that are tailored to the context of a site on a case by case basis. Where the PUD Development Narrative is silent on a requirement, the applicable Zoning Ordinance provisions will be applied.

The PUD proposes a multifamily residential development. The proposed development narrative lists all permitted uses in the T5:5 (Walkable Urban Code) transect district as permitted on the site.

6. **Development Standards**

The PUD proposes development standards designed to accommodate multifamily residential buildings with a maximum building height of 56 with no density limit. However, the proposed building height is of 48 feet and 4 stories, with 515 dwelling units proposed.

The project site has two street frontages along its northern and eastern perimeters. The PUD proposes pedestrian-friendly design with most of the residential buildings facing the adjacent streets and several pedestrian connections are provided to these. All resident and guest parking will be distributed throughout the site.

Below is a summary of the key development standards set forth in the narrative.



Conceptual Site Plan,
Source: Todd + Associates

<u>Development Standards</u>	
<u>Standard</u>	<u>Proposed</u>
<i>Density</i>	No maximum
<i>Building Height</i>	56 feet
<i>Perimeter Building Setbacks</i>	
Washington Street (Primary Frontage)	Minimum: 20 feet Maximum: 30 feet
48th Street (Secondary Frontage)	Minimum: 20 feet Maximum: 30 feet
South	0 feet
West	5 feet
Interior Lot Lines	0 feet
<i>Maximum Lot Coverage</i>	80 percent maximum
<i>Parking</i>	

Residents (Reserved and Unreserved)	901 spaces
Bicycle	Minimum 0.25 spaces per unit for a maximum of 50 spaces
<i>Perimeter Landscape Setbacks</i>	
Washington Street (Primary Frontage)	20 feet minimum
48th Street (Secondary Frontage)	20 feet minimum
South	0 feet
West	5 feet
<i>Open Space</i>	5 percent minimum

7. **Landscape Standards**

The PUD sets forth standards to activate two street frontages (48th Street and Washington Street) with pedestrian-oriented design and street-facing residential units. It also sets forth requirements to maximize the landscaping along these street frontages. Minimum 2-inch and 3-inch caliper trees will be required, planted 20 feet on center or in equivalent groupings along street frontages. Additionally, five shrubs per tree will be provided, and live groundcover to provide 75 percent groundcover at maturity. Furthermore, interior property lines not adjacent to public right-of-way shall be landscaped with minimum 1.5-inch caliper trees planted 25 feet on center or in equivalent groupings, in addition to five shrubs per tree and achieve 50 percent groundcover at maturity.

8. **Design Guidelines**

The PUD proposes a development design that prioritizes the pedestrian. Specifically, it sets forth requirements for frontage types that will activate the street frontages in addition to providing pedestrian connections between residential buildings, street frontages and open space areas, which will have a various amenities.

AREA PLANS, OVERLAY DISTRICTS, AND INITIATIVES

9. **44th Street Corridor Specific Plan**

The site is located within the boundaries of the 44th Street Corridor Specific Plan. Completed in 1991, the 44th Street Corridor Specific Plan established a framework to provide compatibility of new development along 44th Street from McDonald Drive to Sky Harbor International Airport. The Land Use Plan within the Specific Plan designates the subject property for commerce park, which is not consistent with the request. However, the standards proposed in the PUD narrative are compatible with the streetscape, landscaping, and design considerations listed in the plan.

10. [Transit Oriented Development Strategic Policy Framework](#)
The Transit Oriented Development Strategic Policy Framework, originally adopted in 2013, and later amended in 2016 and 2018, identifies policies and place types that are designed to shape walkable and mixed-use environments and focus redevelopment within a quarter mile of high capacity transit stations. The subject site is located less than quarter mile from the 50th Street / Washington Street light rail station, which is identified as a Minor Urban Center place type. A Minor Urban Center is a place type characterized by medium to low intensity uses, with building heights typically from two to five stories, with incentive heights of up to seven stories. Land uses may include entertainment, retail, mid-rise residences and low-rise office developments. The proposed project, with a focus on pedestrian-oriented design, is consistent with the Minor Urban Center place type. Further, the utilization of the Walkable Urban Code for the framework for the PUD is consistent with the policies of the TOD Strategic Policy Framework.
11. [Housing Phoenix Plan](#)
In June 2020, the Phoenix City Council approved the Housing Phoenix Plan. This Plan contains policy initiatives for the development and preservation of housing with a vision of creating a stronger and more vibrant Phoenix through increased housing options for residents at all income levels and family sizes. Phoenix's rapid population growth and housing underproduction has led to a need for over 163,000 new housing units. Current shortages of housing supply relative to demand are a primary reason why housing costs are increasing. The proposed development supports the Plan's goal of preserving or creating 50,000 housing units by 2030 by providing an opportunity for multifamily residential development.
12. [Tree and Shade Master Plan](#)
The Tree and Shade Master Plan has a goal of treating the urban forest as infrastructure to ensure that trees are an integral part of the city's planning and development process. By investing in trees and the urban forest, the city can reduce its carbon footprint, decrease energy costs, reduce storm water runoff, increase biodiversity, address the urban heat island effect, clean the air, and increase property values. In addition, trees can help to create walkable streets and vibrant pedestrian places. The PUD includes standards for enhanced tree sizes along the street frontages, and a requirement for minimum 75 percent live groundcover will help reduce the urban heat island effect.
13. [Complete Streets Guiding Principles](#)
In 2014, the City of Phoenix City Council adopted the Complete Streets Guiding Principles. The principles are intended to promote improvements that provide an accessible, safe, connected transportation system to include all modes, such as bicycles, pedestrians, transit, and vehicles. The development will activate the street frontages, provide pedestrian connections to those frontages and provide enhanced landscaping and shade along the sidewalks.

14. [Comprehensive Bicycle Master Plan](#)

The City of Phoenix adopted the Comprehensive Bicycle Master Plan in 2014 to guide the development of its bikeway system and supportive infrastructure. The Comprehensive Bicycle Master Plan supports options for both short- and long-term bicycle parking as a means of promoting bicyclist traffic to a variety of destinations. The proposal incorporates requirements for bicycle parking to encourage multi-modal transportation.

15. [Zero Waste PHX](#)

The City of Phoenix is committed to its waste diversion efforts and has set a goal to become a zero waste city, as part of the city's overall 2050 Environmental Sustainability Goals. One of the ways Phoenix can achieve this is to improve and expand its recycling and other waste diversion programs. Section 716 of the Phoenix Zoning Ordinance establishes standards to encourage the provision of recycling containers for multifamily, commercial and mixed-use developments meeting certain criteria. The PUD narrative states that recycling containers will be provided on site.

COMMUNITY INPUT SUMMARY

16. At the time this staff report was written, staff did not receive any letters or correspondence regarding the project.

INTERDEPARTMENTAL COMMENTS

17. The Public Transit Department has requested that the developer provide maximum shade for sidewalks and pedestrian pathways. Furthermore, where pedestrian paths cross drive aisles, that they be constructed of materials that visually contrast with parking and drive aisle surfaces. These are addressed in the development narrative.
18. The Street Transportation Department has required that all streets be constructed with all required improvements and comply with current ADA standards. This is addressed in Stipulation No. 2.
19. The Floodplain Management division of the Public Works Department indicated that the site is in a Special Flood Hazard Area (SFHA) called Zone A, on panel 2230 M of the Flood Insurance Rate Maps (FIRM) dated September 18, 2020. Stipulation No. 3 addresses floodplain requirements.
20. This site is located within **CLOSE PROXIMITY TO** the noise contour area of Phoenix Sky Harbor International Airport (PHX). As such, staff is requesting that the developer provide notice to prospective purchasers or tenants regarding the existence and operational characteristics of this airport, that an aviation easement be granted and recorded for the City of Phoenix for the site, that noise mitigation is addressed through building construction, and that the developer provide a No Hazard determination from the FAA prior to construction permit approval. These

requirements are addressed in the development narrative and Stipulation Nos. 4 through 6.

21. The Office of Environmental Programs commented that a construction and demolition landfill was once located on the site and **ADJACENT TO** the southern portion of the site was previously the location of the Olin Matheson Chemical Corporation and Arizona Agrochemical Corporation. The site was granted closure by the Arizona Department of Environmental Quality (ADEQ) based on a risk assessment of exposure to future construction workers and industrial employees, and that contaminated soil was reportedly removed from the site along with various other material including empty 55-gallon drums, underground storage tanks, and pesticide contaminated liquids. The Office of Environmental Programs ~~commented~~ **RECOMMENDS CONSIDERATION** that methane sampling should be completed in the area of any proposed buildings on this property, vapor barriers should be installed for any buildings on this property and if the existing wells are in the way of development, they should be abandoned following the proper Arizona Department of Water Resources regulations. The applicant will follow all **ENVIRONMENTAL** requirements ~~by ADEQ~~ during the permitting and construction process.

OTHER

22. The site is located in an area identified as being archaeologically sensitive. In further review by the City of Phoenix Archaeology Office, it was determined that the Phase I testing conducted on the subject site by the applicant does not warrant additional archaeological testing. However, in the event archaeological materials are encountered during construction, all ground disturbing activities must cease within a 33-foot radius of the discovery and the City of Phoenix Archaeology Office must be notified immediately and allowed time to properly assess the materials. This is addressed in Stipulation No. 7.
23. Staff has not received a completed form for the Waiver of Claims for Diminution in Value of Property under Proposition 207 (A.R.S. 12-1131 et seq.), as required by the rezoning application process. Therefore, a stipulation has been added to require the form be completed and submitted prior to preliminary site plan approval. This is addressed in Stipulation No. 8.
24. Development and use of the site is subject to all applicable codes and ordinances. Zoning approval does not negate other ordinance requirements. Other formal actions such as, but not limited to, zoning adjustments and abandonments, may be required.

Findings

1. The proposal will develop a vacant site and provide additional housing options within proximity to a light rail station and employment uses. The proposed

development is also compatible in intensity, scale, and character with the surrounding area.

2. The project site is appropriately located along an arterial street and within a quarter mile of a light rail station.
3. The proposed PUD sets forth design and development standards that will facilitate pedestrian-oriented design and promote a safer walking environment.

Stipulations

1. An updated Development Narrative for the Banyan Residential 48th Street & Washington PUD reflecting the changes approved through this request shall be submitted to the Planning and Development Department within 30 days of City Council approval of this request. The updated Development Narrative shall be consistent with the Development Narrative date stamped May 23, 2022, as modified by the following stipulations:
 - a. Front cover: Revise the date information on the cover page to the following:

City Council Adopted: [Add Adoption Date]
2. The developer shall construct all streets within and adjacent to the development with paving, curb, gutter, sidewalk, curb ramps, streetlights, median islands, landscaping and other incidentals, as per plans approved by the Planning and Development Department. All improvements shall comply with all ADA accessibility standards.
3. This parcel is in a Special Flood Hazard Area (SFHA) called Zone A, on panel 2230 M of the Flood Insurance Rate Maps (FIRM) dated September 18, 2020. The following requirements shall apply, as approved by the Planning and Development Department:
 - a. The Architect/Engineer is required to show the floodplain boundary limits on the Grading and Drainage plan and ensure that impacts to the proposed facilities have been considered, following the National Flood Insurance Program (NFIP) Regulations (44 CFR Paragraph 60.3). This includes, but not limited to provisions in the latest versions of the Floodplain Ordinance of the Phoenix City Code.
 - b. A copy of the Grading and Drainage Plan shall be submitted to the Floodplain Management section of Public Works Department for review and approval of Floodplain requirements.

- c. The developer shall provide a FEMA approved CLOMR-F or CLOMR prior to issuance of a Grading and Drainage permit.
4. The property owner shall record documents that disclose the existence, and operational characteristics of Phoenix Sky Harbor Airport to future owners or tenants of the property. The form and content of such documents shall be according to the templates and instructions provided which have been reviewed and approved by the City Attorney.
5. The developer shall provide a No Hazard Determination for the proposed development from the FAA pursuant to the FAA's Form-7460 obstruction analysis review process, prior to construction permit approval, as per plans approved by the Planning and Development Department.
6. The developer shall grant and record an aviation easement to the City of Phoenix for the site, per the content and form prescribed by the City Attorney prior to final site plan approval.
7. In the event archaeological materials are encountered during construction, the developer shall immediately cease all ground-disturbing activities within a 33- foot radius of the discovery, notify the City Archaeologist, and allow time for the Archaeology Office to properly assess the materials.
8. Prior to preliminary site plan approval, the landowner shall execute a Proposition 207 waiver of claims form. The waiver shall be recorded with the Maricopa County Recorder's Office and delivered to the City to be included in the rezoning application file for record.

Writer

Sarah Stockham

August 3, 2022

Team Leader

Racelle Escolar

Exhibits


Sketch Map

Aerial Map


Conceptual Site Plan date stamped November 30, 2021

Conceptual Elevations date stamped November 30, 2021 (18 pages)

[Banyan Residential PUD](#) development narrative date stamped May 23, 2022



Z-64-21



APPLICANT'S NAME: Odyssey Group Holdings, LLC

APPLICATION NO. Z-64-21

DATE: 10/11/2021
REVISION DATES:

GROSS AREA INCLUDING 1/2 STREET
AND ALLEY DEDICATION IS APPROX.

17.82 Acres

AERIAL PHOTO &
QUARTER SEC. NO.

QS 10-38

ZONING MAP

F-11

REQUESTED CHANGE:

FROM: A-2 (17.82 a.c.)

TO: PUD (17.82 a.c.)

MULTIPLES PERMITTED

A-2

PUD

CONVENTIONAL OPTION

N/A




N/A

* UNITS P.R.D. OPTION

N/A

583

* Maximum Units Allowed with P.R.D. Bonus



APPLICANT'S NAME: Odyssey Group Holdings, LLC		REQUESTED CHANGE:	
APPLICATION NO. Z-64-21		FROM: A-2 (17.82 a.c.)	
DATE: 10/11/2021 REVISION DATES:		TO: PUD (17.82 a.c.)	
GROSS AREA INCLUDING 1/2 STREET AND ALLEY DEDICATION IS APPROX. 17.82 Acres			
AERIAL PHOTO & QUARTER SEC. NO. QS 10-38		ZONING MAP F-11	
MULTIPLES PERMITTED A-2 PUD		CONVENTIONAL OPTION N/A N/A	
		* UNITS P.R.D. OPTION N/A 583	

* Maximum Units Allowed with P.R.D. Bonus



TODD + ASSOCIATES
602-952-8280 / TODDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

NOV 30 2021

**Planning & Development
Department**

**BUILDING 1 - EXTERIOR
ELEVATIONS**
Preliminary Not For Construction


A4.1.1



ARCHITECT: TDD
PWP NO. 2102206
DESIGN NO. 2102206
ZONING MAP F11
PROJECT LOCATION: SWC 48TH ST. & E. WASHINGTON ST.
PRELIMINARY MEETING: 06.11.2021


4 BUILDING 1 - SOUTH ELEVATION

SCALE: 1/16" = 1'-0"




2 BUILDING 1 - WEST ELEVATION

SCALE: 1/16" = 1'-0"




1 BUILDING 1 - EAST ELEVATION

SCALE: 1/16" = 1'-0"



LOCATION	MANUFACTURER	COLOR
A	PAINT #1	SW 657
B	PAINT #2	SW 657
C	ACCENT PAINT	SW 657
D	PAINT #3	SW 657
E	PAINT #4	SW 657
F	PAINT #5	SW 657
G	PAINT #6	SW 657
H	PAINT #7	SW 657
I	PAINT #8	SW 657
J	PAINT #9	SW 657
K	PAINT #10	SW 657
L	PAINT #11	SW 657
M	PAINT #12	SW 657
N	PAINT #13	SW 657
O	PAINT #14	SW 657
P	PAINT #15	SW 657
Q	PAINT #16	SW 657
R	PAINT #17	SW 657
S	PAINT #18	SW 657
T	PAINT #19	SW 657
U	PAINT #20	SW 657
V	PAINT #21	SW 657
W	PAINT #22	SW 657
X	PAINT #23	SW 657
Y	PAINT #24	SW 657
Z	PAINT #25	SW 657

FLOOR KEYMAP MAP





TODD + ASSOCIATES
602-952-8280 / TODDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona
PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

NOV 30 2021

Planning & Development
Department

BUILDING 1 - EXTERIOR
ELEVATIONS
Preliminary Not For Construction


A4.1.1



LOCATION	MANUFACTURER	COLOR
A	SHERRILL WILLIAMS	SW 502
B	SHERRILL WILLIAMS	WHITE
C	SHERRILL WILLIAMS	SW 502
D	SHERRILL WILLIAMS	SW 502
E	SHERRILL WILLIAMS	SW 502
F	SHERRILL WILLIAMS	SW 502


1 BUILDING 1 - EAST ELEVATION

SCALE: 1/16" = 1'-0"




2 BUILDING 1 - WEST ELEVATION

SCALE: 1/16" = 1'-0"



3 BUILDING 1 - NORTH ELEVATION

SCALE: 1/16" = 1'-0"




4 BUILDING 1 - SOUTH ELEVATION


SCALE: 1/16" = 1'-0"



ARCHITECT
TODD ASSOCIATES
21144 N. 21ST AVE.
PHOENIX, AZ 85016
P.L.L.C.
PRELIMINARY MEETING
08.11.2021



FLOOR KEY MAP




Preliminary Not For Construction

Planning & Development
Department

A4.2.1


LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7757 WHITE REFLECTIVE
B	SHERWIN WILLIAMS	SW 6005 "TOLSTONE"
C	SHERWIN WILLIAMS	SW 9133 (ACCENT) "JASPER STONE"
D	ACCENT PAINT	SW 9133 (ACCENT) "JASPER STONE"
E	PAVING	SPURITE SPACE SAND
F	PAVING	PAVING
G	PAVING	PAVING
H	PAVING	PAVING
I	PAVING	PAVING
J	PAVING	PAVING
K	PAVING	PAVING
L	PAVING	PAVING
M	PAVING	PAVING
N	PAVING	PAVING
O	PAVING	PAVING
P	PAVING	PAVING
Q	PAVING	PAVING
R	PAVING	PAVING
S	PAVING	PAVING
T	PAVING	PAVING
U	PAVING	PAVING
V	PAVING	PAVING
W	PAVING	PAVING
X	PAVING	PAVING
Y	PAVING	PAVING
Z	PAVING	PAVING




FLOOR KEY MAP



1 BUILDING 2 - NORTH ELEVATION



2 BUILDING 2 - NORTHEAST ELEVATION



4 BUILDING 2 - NORTH ELEVATION



3 BUILDING 2 - EAST ELEVATION



5 BUILDING 2 - WEST ELEVATION

TODD + ASSOCIATES
602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona
PUD SUBMITTAL
06-23-2021

CITY OF PHOENIX

NOV 30 2021
Planning & Development
Department

BUILDING 2 - EXTERIOR ELEVATIONS
Preliminary Not For Construction





ARCHITECT: SWC
PWP NO. 21-1444
ZONING MAP: F11
PRELIMINARY MEETING: 08-11-2021

A4.2.1


LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7757 WHITE REFLECTIVE
B	SHERWIN WILLIAMS	SW 4205 "TOLSTONE"
C	SHERWIN WILLIAMS	SW 9133 ACCENT "JASPER STONE"
D	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
E	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
F	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
G	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
H	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
I	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
J	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
K	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
L	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
M	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
N	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
O	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
P	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
Q	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
R	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
S	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
T	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
U	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
V	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
W	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
X	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
Y	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"
Z	SHERWIN WILLIAMS	SW 4406 "TOLSTONE"

COLOR KEY MAP MAP




1 BUILDING 2 - SOUTHWEST ELEVATION

SCALE: 1/16" = 1'-0"



3 BUILDING 2 - WEST ELEVATION

SCALE: 1/16" = 1'-0"



2 BUILDING 2 - SOUTH ELEVATION

SCALE: 1/16" = 1'-0"



602-952-8280 / TODDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

BUILDING 2 - EXTERIOR ELEVATIONS

Preliminary Not For Construction



ARCHITECT NO. 2100127
PAP. NO. 2100204
DESIGN NO. 211146
DRAWING NO. 211146
DATE: 06-11-2021
PROJECT: APARTMENTS @ SWC 48TH ST. & E. WASHINGTON ST.
SHEET: 20-2025-00

A4.2.2

NOV 30 2021

Planning & Development Department




6 BUILDING 3 - WEST ELEVATION
SCALE: 1/16" = 1'-0"



4 BUILDING 3 - EAST ELEVATION
SCALE: 1/16" = 1'-0"




1 BUILDING 3 - WEST ELEVATION
SCALE: 1/16" = 1'-0"




7 BUILDING 3 - SOUTHWEST ELEVATION
SCALE: 1/16" = 1'-0"




2 BUILDING 3 - NORTH ELEVATION
SCALE: 1/16" = 1'-0"



8 BUILDING 3 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"




5 BUILDING 3 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"



3 BUILDING 3 - NORTHEAST ELEVATION
SCALE: 1/16" = 1'-0"

LOCATION	MANUFACTURER	COLOR
A	PAINT #1	SW 7537 WHITE REFLECTIVE
B	PAINT #2	SW 4005 'TOLSTONE'
C	ACCENT PAINT	SW P33 ACCENT 'JAPANESE STONE'
D	CMU	SPRINKLE SPACE BOARD
E	ISING	CHERRYWOOD
F	AWNING & RAILING	SW 4005 'TOLSTONE'
G	ALUMINUM SCREEN	ALUMINUM SCREEN



ADSV/DSV NO.	2100187
PAPP NO.	2100064
PROJECT NO.	17-00000000
VILLAGE	CAMERON EAST
QUARTER ACTION NO.	17-00000000
PRE-ATTENDANCE MEETING	05-11-2021



TODD + ASSOCIATES
602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.


Phoenix, Arizona
PUD SUBMITTAL
06-23-2021

CITY OF PHOENIX

NOV 30 2021
Planning & Development
Department

**BUILDING 3 - EXTERIOR
ELEVATIONS**
Preliminary Not For Construction

A4.3.1



A4.4.1



TODD + ASSOCIATES

602-952-8280 / TODDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

NOV 30 2021

Planning & Development
Department

**BUILDING 4 - EXTERIOR
ELEVATIONS**

Preliminary Not For Construction



1 BUILDING 4 - WEST ELEVATION

SCALE: 1/16" = 1'-0"



2 BUILDING 4 - NORTH ELEVATION

SCALE: 1/16" = 1'-0"



3 BUILDING 4 - EAST ELEVATION

SCALE: 1/16" = 1'-0"




ARCHITECT NO.
13487
DATE: 06-23-21
DRAWING NO.
20-2025-00
PROJECT NAME
APARTMENTS @ SWC 48TH ST. & E. WASHINGTON ST.
PREPARED FOR
BANYAN RESIDENTIAL

ARCHITECT NO.
13487
DATE: 06-23-21
DRAWING NO.
20-2025-00
PROJECT NAME
APARTMENTS @ SWC 48TH ST. & E. WASHINGTON ST.
PREPARED FOR
BANYAN RESIDENTIAL



LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7537
B	SHERWIN WILLIAMS	WHITE REFLECTIVE
C	SHERWIN WILLIAMS	SW 6005
D	SHERWIN WILLIAMS	TOULSTONE
E	SHERWIN WILLIAMS	SW 9133
F	SHERWIN WILLIAMS	JASPER STONE
G	SHERWIN WILLIAMS	SW 6005
H	SHERWIN WILLIAMS	TOULSTONE
I	SHERWIN WILLIAMS	SW 6005
J	SHERWIN WILLIAMS	TOULSTONE
K	SHERWIN WILLIAMS	SW 6005
L	SHERWIN WILLIAMS	TOULSTONE
M	SHERWIN WILLIAMS	SW 6005
N	SHERWIN WILLIAMS	TOULSTONE
O	SHERWIN WILLIAMS	SW 6005
P	SHERWIN WILLIAMS	TOULSTONE
Q	SHERWIN WILLIAMS	SW 6005
R	SHERWIN WILLIAMS	TOULSTONE
S	SHERWIN WILLIAMS	SW 6005
T	SHERWIN WILLIAMS	TOULSTONE
U	SHERWIN WILLIAMS	SW 6005
V	SHERWIN WILLIAMS	TOULSTONE
W	SHERWIN WILLIAMS	SW 6005
X	SHERWIN WILLIAMS	TOULSTONE
Y	SHERWIN WILLIAMS	SW 6005
Z	SHERWIN WILLIAMS	TOULSTONE

FLOOR KEYMAP-MAP



A4.4.1

FLOOR KEY MAP MAP



Preliminary Not For Construction


**Planning & Development
Department**

13467
GARY D.
TODO
06-23-21
Date signed
ARIZONA
REGISTERED ARCHITECT
CERTIFICATE NO.

A4.4.2

LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7537
B	SHERWIN WILLIAMS	SW 4005
C	SHERWIN WILLIAMS	SW 4005
D	SHERWIN WILLIAMS	SW 1131 (ACCENT)
E	SHERWIN WILLIAMS	SW 1131 (ACCENT)
F	SHERWIN WILLIAMS	SW 1131 (ACCENT)
G	SHERWIN WILLIAMS	SW 1131 (ACCENT)
H	SHERWIN WILLIAMS	SW 1131 (ACCENT)
I	SHERWIN WILLIAMS	SW 1131 (ACCENT)
J	SHERWIN WILLIAMS	SW 1131 (ACCENT)
K	SHERWIN WILLIAMS	SW 1131 (ACCENT)
L	SHERWIN WILLIAMS	SW 1131 (ACCENT)
M	SHERWIN WILLIAMS	SW 1131 (ACCENT)
N	SHERWIN WILLIAMS	SW 1131 (ACCENT)
O	SHERWIN WILLIAMS	SW 1131 (ACCENT)
P	SHERWIN WILLIAMS	SW 1131 (ACCENT)
Q	SHERWIN WILLIAMS	SW 1131 (ACCENT)
R	SHERWIN WILLIAMS	SW 1131 (ACCENT)
S	SHERWIN WILLIAMS	SW 1131 (ACCENT)
T	SHERWIN WILLIAMS	SW 1131 (ACCENT)
U	SHERWIN WILLIAMS	SW 1131 (ACCENT)
V	SHERWIN WILLIAMS	SW 1131 (ACCENT)
W	SHERWIN WILLIAMS	SW 1131 (ACCENT)
X	SHERWIN WILLIAMS	SW 1131 (ACCENT)
Y	SHERWIN WILLIAMS	SW 1131 (ACCENT)
Z	SHERWIN WILLIAMS	SW 1131 (ACCENT)

1 FLOOR KEYMAP-WA-PA



1 BUILDING 4 - SOUTH ELEVATION

SCALE 1/16" = 1'-0"




2 BUILDING 4 - SOUTH ELEVATION

SCALE 1/16" = 1'-0"



3 BUILDING 4 - NORTH ELEVATION

SCALE 1/16" = 1'-0"



4 BUILDING 4 - SOUTHEAST ELEVATION

SCALE 1/16" = 1'-0"

5 BUILDING 4 - NORTH ELEVATION

SCALE 1/16" = 1'-0"

TODD + ASSOCIATES

602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartment @ SWC 48th St. & E. Washington St.

Phoenix, Arizona
PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX


BUILDING 4 - EXTERIOR
ELEVATIONS
Preliminary Not For Construction



ARCHITECT	NOV 17, 2020
DATE	11/17/2020
PROJECT NO.	21-144
PROJECT NAME	SWC 48TH ST & E WASHINGTON ST
PROJECT LOCATION	PHOENIX, AZ
PROJECT TYPE	RESIDENTIAL
PROJECT STATUS	PRELIMINARY
PROJECT DATE	06-11-2021

A4.4.2

NOV 30 2021
Planning & Development
Department



USD KIVA NO.
 VILLAGE
 ZONING MAP
 QUARTER SECTION
 PRE. A BELLIC A YC

21-1644
CAMELBA
F11
10-38
05-11-30

Preliminary Not For Construction

Planning & Development
Department



TODD + ASSOCIATES

602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona


PUD SUBMITTAL

06-23-2021

BUILDING 5 - EXTERIOR ELEVATIONS
Preliminary Not For Construction

NOV 30 2021

Planning & Development Department




1 BUILDING 5 - WEST ELEVATION

SCALE: 1/16" = 1'-0"



2 BUILDING 5 - NORTH ELEVATION

SCALE: 1/16" = 1'-0"



3 BUILDING 5 - EAST ELEVATION

SCALE: 1/16" = 1'-0"



ARCH/DEV NO.
2100187
APP NO.
2100064
PROJECT NO.
13487
VILLAGE
CAMERBACK EAST
DRAWING NO.
17-1
DATE
10-18
PREPARED BY
GARY D. WILLIAMS
PREPARED FOR
BANYAN RESIDENTIAL
PREPARED DATE
06-11-2021

TODD + ASSOCIATES

602-952-8280 / TCDDASSOC.COM
20-2025-00

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

BUILDING 5 - EXTERIOR ELEVATIONS
Preliminary Not For Construction

NOV 30 2021

Planning & Development Department



TODD + ASSOCIATES

602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL



06-23-2021

BUILDING 5 - EXTERIOR ELEVATIONS
Preliminary Not For Construction


NOV 30 2021

Planning & Development Department

LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7757 WHITE REFLECTIVE
B	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
C	SHERWIN WILLIAMS	SW 9133 (ACCENT) "JASPER STONE"
D	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
E	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
F	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
G	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
H	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
I	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
J	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
K	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
L	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
M	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
N	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
O	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
P	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
Q	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
R	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
S	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
T	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
U	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
V	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
W	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
X	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
Y	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"
Z	SHERWIN WILLIAMS	SW 4005 "TOLSTONE"




1 BUILDING 5 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"




3 BUILDING 5 - NORTH ELEVATION
SCALE: 1/16" = 1'-0"



5 BUILDING 5 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"



2 BUILDING 5 - NORTH ELEVATION
SCALE: 1/16" = 1'-0"



4 BUILDING 5 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"

TODD + ASSOCIATES
602-952-8280 / TCDDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona

PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

BUILDING 5 - EXTERIOR ELEVATIONS
Preliminary Not For Construction

NOV 30 2021

Planning & Development Department





ADSV/DSV NO. 2100187
APP NO. 2100064
PROJECT NO. 2100064
VILLAGE CAMERON EAST
DRAWING NO. 2100064-01
DATE 10-11-2021
PRE-ATTENTION MEETING 08-11-2021


A4.5.2

LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7757
B	SHERWIN WILLIAMS	SW 7757
C	SHERWIN WILLIAMS	SW 6905
D	SHERWIN WILLIAMS	TOUCANE
E	SHERWIN WILLIAMS	SW 9151 (ACCENT)
F	SHERWIN WILLIAMS	TOUCANE
G	SHERWIN WILLIAMS	TOUCANE
H	SHERWIN WILLIAMS	TOUCANE
I	SHERWIN WILLIAMS	TOUCANE
J	SHERWIN WILLIAMS	TOUCANE
K	SHERWIN WILLIAMS	TOUCANE
L	SHERWIN WILLIAMS	TOUCANE
M	SHERWIN WILLIAMS	TOUCANE
N	SHERWIN WILLIAMS	TOUCANE
O	SHERWIN WILLIAMS	TOUCANE
P	SHERWIN WILLIAMS	TOUCANE
Q	SHERWIN WILLIAMS	TOUCANE
R	SHERWIN WILLIAMS	TOUCANE
S	SHERWIN WILLIAMS	TOUCANE
T	SHERWIN WILLIAMS	TOUCANE
U	SHERWIN WILLIAMS	TOUCANE
V	SHERWIN WILLIAMS	TOUCANE
W	SHERWIN WILLIAMS	TOUCANE
X	SHERWIN WILLIAMS	TOUCANE
Y	SHERWIN WILLIAMS	TOUCANE
Z	SHERWIN WILLIAMS	TOUCANE


FLOOR KEYMAP MAP




1 BUILDING 6 - WEST ELEVATION




2 BUILDING 6 - NORTH ELEVATION



4 BUILDING 6 - SOUTH ELEVATION



3 BUILDING 6 - EAST ELEVATION



5 BUILDING 6 - NORTHEAST ELEVATION



MEET/ISSUE NO.	210117
DATE	06/11/2021
PROJECT NO.	210306
PROJECT NAME	CAMERACK EAST
VILLAGE	10-38
QUARTER SECTION NO.	10-38
PRELIMINARY MEETING	06/11/2021



TODD + ASSOCIATES
602-952-8280 / TODDASSOC.COM
20-2025-00



BANYAN RESIDENTIAL

Apartments @ SWC 48th St. & E. Washington St.

Phoenix, Arizona
PUD SUBMITTAL

06-23-2021

CITY OF PHOENIX

NOV 30 2021



Planning & Development Department

BUILDING 6 - EXTERIOR ELEVATIONS
Preliminary Not For Construction


A4.6.1

LOCATION	MANUFACTURER	COLOR
A	SHERWIN WILLIAMS	SW 7357 WHITE REEL
B	SHERWIN WILLIAMS	SW 4005 TULLOCH
C	ACCENT PAINT	SW 9133 PA JASPER DR
D	CMU	SPRINKLE SPACE BOND BRICK
E	IRONING	PAC CLAD TIGHT PANEL
F	AVENINGS & BLINDS	SHERWIN WILLIAMS TULLOCH
G	SCOREBOARD	AMERICA
H	DAIRY BROT	

FLOOR KEYMAP-MAP



1 BUILDING 6 - WEST ELEVATION
SCALE: 1/16" = 1'-0"




4 BUILDING 6 - SOUTH ELEVATION
SCALE: 1/16" = 1'-0"



2 BUILDING 6 - NORTH ELEVATION
SCALE: 1/16" = 1'-0"



3 BUILDING 6 - EAST ELEVATION
SCALE: 1/16" = 1'-0"



5 BUILDING 6 - NORTHEAST ELEVATION
SCALE: 1/16" = 1'-0"

TODD + ASSOCIATES
602-952-8280 / TCDDASSOC.COM
20-2025-00

BANYAN RESIDENTIAL

Apartment @ SWC 48th St. & E. Washington St.
Phoenix, Arizona
PUD SUBMITTAL
06-23-2021

BUILDING 6 - EXTERIOR ELEVATIONS
Preliminary Not For Construction

NOV 30 2021
Planning & Development Department

A4.6.1



ADVISORY/REV. NO. 2100187
PAPP NO. 2100094
VILLAGE CAMELEBAC
DRAWING NO. 10-38
PRELIMINARY MEETING 08-11-2021